

I-75 at Emory Road

Signage and Roadscapes

STATE 47 PLM-F1-109
FED # STP-BN-475-3(109)
TDOT PNM 105525.23

10. NO SMOKING
TENNESSEE ONE CALL SYSTEM
BEFORE YOU DIG CALL
1-800-831-1111

INSTALLATION SCHEDULE

FROM	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEPT	OCT	NOV	DEC
ALL TREE PLANTING												

Scale: 1" = 30'-0"

TYPE STATE # 13
FEDERAL # 13

PROJECT NO. 47PLM-F1-109
STP-BN-475-3(156)

SHEET NO. 1

DATE: March 31, 2015

LANDSCAPE IMPROVEMENT PLAN

Interstate 76 & Emory Road

PLANT SCHEDULE

ITEM NUMBER	QTY	QTY	BOTANICAL NAME	COMMON NAME	UNIT	CONT.	SIZE	HEIGHT	REMARKS
802-11-42	BC	3	Fernandus dactyloides	RED CYPRESS	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-43	BC	18	Quercus laevis	WHITE OAK	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-44	BC	12	Cercis canadensis	RED BUD	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-45	BC	12	Acer rubrum	RED MAPLE	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-46	BC	2	Thuja occidentalis	WAXY BUSH	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-47	BC	1	Maquignia grandifolia	SOUTHERN MAGNOLIA	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-48	BC	1	Liquidambar styraciflua	FLAME TREE	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-49	BC	1	Pinus strobus	WHITE PINE	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-50	BC	14	Quercus prinus	YELLOW OAK	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-51	BC	1	Claytonia virginica	YELLOW PINE	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-52	BC	1	Amelanchier canadensis	AMERICAN HOLLY	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-53	BC	1	Quercus laevis	WHITE OAK	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-54	BC	12	Banksia laevis	SWAMP GREEN VELVET BUSH	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-55	BC	24	Banksia laevis	SWAMP GREEN VELVET BUSH	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-56	BC	1	Quercus laevis	WHITE OAK	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown
802-11-57	BC	1	Quercus laevis	WHITE OAK	EA	5-6'	1.5'-2.0' CM	2-4'	Container Grown

SPECIAL NOTES:

FOR GENERAL NOTES PLEASE REFER TO TDOT GENERAL NOTES. FOR LATEST NOTES PLEASE GO TO www.tdot.state.tn.us/contractors/GENERALNOTES/PDF/GENERALNOTES.pdf.

- UNDERGROUND UTILITIES: A. UNDERGROUND UTILITIES HAVE NOT BEEN VERIFIED BY THE OWNER. LANDSCAPE ARCHITECT, OR THEIR REPRESENTATIVE, BEFORE YOU DO CALL TENNESSEE ONE CALL SYSTEM 1-800-831-1111.
- THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK. AND AGREE TO BE RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT RESULT FROM THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY UNDERGROUND UTILITIES TO REMAIN.
- THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS TO ENSURE THAT THE NEW WORK SHALL FIT INTO THE EXISTING SITE IN THE MANNER INTENDED AND AS SHOWN ON THE DRAWINGS. SHOULD ANY CONDITIONS EXIST THAT ARE CONTRARY TO THOSE ON THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE PRIOR TO PERFORMING ANY WORK IN THE AREA INVOLVING DIFFERENCES. NOTIFICATION SHALL BE MADE IN THE FORM OF A DRAWING OR SKETCH INDICATING FIELD MEASUREMENTS AND NOTES RELATING TO THE AREA.
- THE LANDSCAPE CONTRACTOR WILL BE FINANCIALLY LIABLE FOR ANY DAMAGE CAUSED TO NON-PAYMENT, CURBS, OR OTHER COMPLETED CONSTRUCTION ITEMS INCURRED DURING THE LANDSCAPE INSTALLATION.
- THE LANDSCAPE CONTRACTOR IS TO PERFORM A THOROUGH CLEANUP AND QUALITY CONTROL INSPECTION.
- THE LANDSCAPE CONTRACTOR IS SUBJECT TO RANDOM INSPECTIONS BY TDOT OR A TDOT REPRESENTATIVE AT ANY TIME DURING THE INSTALLATION PROCESS. WORK NOT IN COMPLIANCE WITH PLANS WILL BE REMOVED AND BROUGHT INTO COMPLIANCE.

LANDSCAPE NOTES:

- PLANTING BEDS AND PLANT LOCATIONS SHALL BE STAKED BY THE LANDSCAPE CONTRACTOR. THE LANDSCAPE CONTRACTOR SHALL NOTIFY TDOT OR A TDOT REPRESENTATIVE FOR APPROVAL PRIOR TO INSTALLATION OF THE PLANTS.
- PLANTING BEDS SHALL BE CLEARED OF ALL GRASS AND WEEDS PRIOR TO INSTALLATION OF PLANTS. INCLUDING SPRAYING HERBICIDE TO KILL ALL OTHERS DISTURBED PLANTS. PLANT BEDS SHALL BE PREPARED AS CALLED FOR IN PLANTING DETAILS AND AS NOTED ON PLANS.
- ANY OTHER DISTURBED AREAS ARE TO BE SEEDS AS PER THE PLANS. ADDITIONAL SEEDING, IF REQUIRED, WILL BE AS DIRECTED BY TDOT OR A TDOT REPRESENTATIVE.
- PLANTING BEDS SHALL HAVE A THREE (3) INCH SHREDDED HARDWOOD BARK MULCH OVER THE ENTIRE BED, UNLESS OTHERWISE NOTED ON THE DRAWINGS.
- PRIOR TO PLANTING, ALL MULCH TREE RINGS SHALL BE TREATED WITH A WATER-SOLUBLE HERBICIDE FOR THE NON-SELECTIVE CONTROL OF ANNUAL AND PERENNIAL WEEDS PRIOR TO PLANTING.
- ALL TREE PLANTING PITS SHALL BE BACKFILLED WITH A PLANTING SOIL MIXTURE OF 80% ORIGINAL SOIL AND 20% TOPSOIL, THOROUGHLY MIXED. SAMPLE OF MIXTURE TO BE APPROVED BY TDOT OR A TDOT REPRESENTATIVE PRIOR TO INSTALLATION.
- ALL PLANTED AREAS ARE TO BE FERTILIZED WITH GRANULAR FERTILIZER LANDSCAPE CONTRACTOR IS TO PROVIDE SOIL TEST RESULTS AND PROPOSED FERTILIZER APPLICATION RATES TO TDOT OR A TDOT REPRESENTATIVE FOR APPROVAL. SOIL TEST SAMPLES SHALL BE TAKEN 100 FEET O.D. ON BOTH SIDES OF THE SUBMITTING SOIL TEST SAMPLE.
- ALL PLANT MATERIAL IS TO BE NURSERY GROWN AND TO COMPLY WITH AMERICAN STANDARDS FOR HEDGERY STOCK.
- SPRAY TREES WITH AN ANTI-DESICCANT IF FOLIAGE IS PRESENT.
- EVERGREEN TREES SHALL BE PLANTED IN THE SAME MANNER AS DECIDUOUS MATERIAL. IS PLANTED.
- DO NOT PRUNE ANY PLANT MATERIAL UNTIL IT HAS BEEN INSPECTED AND ACCEPTED BY TDOT OR A TDOT REPRESENTATIVE.
- ALL LANDSCAPE MATERIAL SHALL BE APPROVED BY TDOT OR A TDOT REPRESENTATIVE CONTRACTORS HOLDING BIDS OR AT THIS SITE. IT SHALL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR TO NOTIFY TDOT OR A TDOT REPRESENTATIVE OF THE AVAILABILITY OF THE MATERIALS TO BE INSPECTED.
- ALL MATERIALS INSPECTED ON THE SITE AND FOUND TO BE UNACCEPTABLE SHALL BE REMOVED FROM THE SITE ON THE DAY OF INSPECTION.
- FIELD CHANGES MUST BE APPROVED IN WRITING BY TDOT OR A TDOT REPRESENTATIVE BEFORE INSTALLATION. MATERIALS MAY BE VIEWED AT LANDSCAPE ARCHITECT FOR POSSIBLE RELOCATION ON SITE. THE LANDSCAPE CONTRACTOR IS TO NOTIFY THE LANDSCAPE ARCHITECT FORTY-EIGHT (48) HOURS BEFORE BEGINNING WORK.
- ALL PLANT MATERIAL SHALL BE SUPPLIED BY APPROPRIATE SOURCES TO PREVENT UNCLE STRESS OR PROLONGED ACCLIMATIZATION WHICH WOULD INHIBIT PLANT GROWTH.
- LANDSCAPE CONTRACTOR IS TO VERIFY PLANT QUANTITIES SHOWN ON PLAN AND IN PLANT LIST. IF DISCREPANCIES OCCUR, LANDSCAPE CONTRACTOR IS TO NOTIFY LANDSCAPE ARCHITECT IMMEDIATELY. QUANTITIES SHOWN ON PLAN TAKE PRECEDENCE.
- REFER TO PLANTING SCHEDULE FOR ACCEPTABLE TIMES FOR INSTALLING PLANT MATERIALS.

TDOT PNM 105525.23