



OFFICE OF COUNTY MAYOR GLENN JACOBS

Procurement Division, 1000 N. Central Street, Suite 100, Knoxville, TN 37917

Knox County Procurement Division Addendum II to Invitation for Bids 3380 Murphy Road Turn Lanes

Addendum Date: March 23, 2023

Buyer: Brian Hubbs

Opening Date: March 28, 2023 at 4:00 PM

Total Page(s): Two (2)

This addendum shall become a part of the project plans and specifications and shall be acknowledged on the bid form.

CLARIFICATIONS

Plan Sheet 2B Revision:

Plan Sheet 2B that was issued in Addendum I did not reflect the correct quantities in the footnotes. **Please use the revised Plan Sheet 2B attached to this Addendum II.** Footnote quantities have been corrected.

End of Addendum II.



A handwritten signature in blue ink, appearing to read "B. Hubbs".

Brian Hubbs
Construction and Contract Specialist
Knox County Procurement Division

| FOOT NOTES | ITEM NO. | DESCRIPTION | UNIT | QTY. |
|------------|-------------|--|------|------|
| | 105-01 | CONSTRUCTION STAKES, LINES AND GRADES | LS | 1 |
| | 201-01 | CLEARING AND GRUBBING | LS | 1 |
| 1 | 202-02.04 | REMOVAL OF PIPE (SIDE DRAINS) | L.F. | 162 |
| 2 | 203-01 | ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED) | C.Y. | 56 |
| | 203-03 | BORROW EXCAVATION (UNCLASSIFIED) | C.Y. | 107 |
| | 209-08.02 | TEMPORARY SILT FENCE (WITH BACKING) | L.F. | 1132 |
| | 209-08.08 | ENHANCED ROCK CHECK DAM | EACH | 2 |
| 3 | KC303-01.01 | MINERAL AGGREGATE, TYPE "A" BASE, GRADING "D" | S.Y. | 1528 |
| 4 | 303-10.01 | MINERAL AGGREGATE (SIZE 57) | TON | 30 |
| 5 | KC307-01.01 | ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING "A" | S.Y. | 1043 |
| 6 | KC307-01.08 | ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING "B-M2" | S.Y. | 799 |
| | KC402-01 | BITUMINOUS MATERIAL FOR PRIME COAT (PC) (RATE 0.35 GAL./SQ. YD.) | TON | 1.6 |
| | KC403-01 | BITUMINOUS MATERIAL FOR TACK COAT (TC) (RATE 0.07 GAL./SQ. YD.) | TON | 1.4 |
| 7 | KC411-01.10 | ASPHALT CONCRETE MIX (PG64-22) (ACS) GRADING "D" | S.Y. | 3877 |
| 8 | 607-39.02 | 18" PIPE CULVERT (SIDE DRAIN) | L.F. | 213 |
| | 611-07.56 | 18IN ENDWALL (CROSS DRAIN) 6:1 | EACH | 4 |
| 9 | 703-01 | PORTLAND CEMENT CONCRETE DITCH PAVING | C.Y. | 22 |
| 10 | 705-06.20 | TANGENT ENERGY ABSORBING TERM MASH TL-2 | EACH | 1 |
| 11 | 709-05.06 | MACHINED RIP-RAP (CLASS A-1) | TON | 159 |
| | 712-01 | TRAFFIC CONTROL | LS | 1 |
| | 712-04.01 | FLEXIBLE DRUMS (CHANNELIZING) | EACH | 70 |
| | 712-06 | SIGNS (CONSTRUCTION) | S.F. | 432 |
| | 716-02.04 | PLASTIC PAVEMENT MARKING(CHANNELIZATION STRIPING) | S.Y. | 12 |
| | 716-02.06 | PLASTIC PAVEMENT MARKING (TURN LANE ARROW) | EACH | 4 |
| | 716-05.20 | PAINTED PAVEMENT MARKING (6" LINE) | L.M. | 1.1 |
| | 716-05.21 | PAINTED PAVEMENT MARKING(4" DOTTED LINE) | L.F. | 241 |
| | 716-12.02 | ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE) | L.M. | 1.1 |
| | 716-12.05 | ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE) | L.F. | 241 |
| | 717-01 | MOBILIZATION | LS | 1 |
| 12 | 740-10.03 | GEOTEXTILE (TYPE III)(EROSION CONTROL) | S.Y. | 380 |
| | 740-11.01 | TEMPORARY SEDIMENT TUBE 8IN | L.F. | 165 |
| | 801-02 | SEEDING (WITHOUT MULCH) | UNIT | 15 |
| | 801-03 | WATER (SEEDING & SODDING) | M.G. | 2 |
| | 805-12.02 | EROSION CONTROL BLANKET (TYPE II) | S.Y. | 1590 |

FOOTNOTES:

- 1 INCLUDES REMOVAL OF 80' OF PIPE AT SHANNON VALLEY FARMS BLVD AND 82' OF PIPE AT HORSESTALL DRIVE
- 2 EXCAVATION FOR CULVERT INLET PROTECTION (TYPE 1) INSTALLATION
- 3 INCLUDES 752 S.Y. FOR SHANNON VALLEY FARMS BLVD AND 776 S.Y. FOR HORSESTALL DRIVE
- 4 USED FOR CULVERT INLET PROTECTION (TYPE 1) INSTALLATION
- 5 INCLUDES 523 S.Y. FOR SHANNON VALLEY FARMS BLVD AND 520 S.Y. FOR HORSESTALL DRIVE
- 6 INCLUDES 408 S.Y. FOR SHANNON VALLEY FARMS BLVD AND 391 S.Y. FOR HORSESTALL DRIVE
- 7 INCLUDES 1978 S.Y. FOR SHANNON VALLEY FARMS BLVD AND 1899 S.Y. FOR HORSESTALL DRIVE
- 8 INCLUDES 122' OF PIPE AT SHANNON VALLEY FARMS BLVD AND 91' OF PIPE AT HORSESTALL DRIVE
- 9 ASSUMES 6" DEPTH FOR CONCRETE
- 10 FOLLOW TDOT STD. DWG. S-GRT -2 AND S-GRT -2R
- 11 USED FOR CULVERT INLET PROTECTION (TYPE 1) INSTALLATION
- 12 USED FOR CULVERT INLET PROTECTION (TYPE 1) INSTALLATION

| | | |
|--|-----------------|------------|
| PAVEMENT QUANTITY AND FOOTNOTE ADJUSTMENT | | 03/21/2023 |
| REVISIONS | DATE | |
|  CONSULTING ENGINEERS · FIELD SURVEYORS TEL 865.670.8555 8550 Kingston Pike WWW.CANNON-CANNON.COM Knoxville, TN 37919 | | |
| CLIENT: | | |
| KNOX COUNTY DEPARTMENT OF ENGINEERING AND PUBLIC WORKS | | |
| PROJECT: | | |
| MURPHY ROAD TURN LANES | | |
| ESTIMATED ROADWAY QUANTITIES | | |
|  | CCI PROJECT NO. | 00263-0104 |
| | DATE | 09-16-22 |
| | P.M. | WAS |
| | DRAWN | AED |
| | Q.C. | WAS |
| | | 2B |